BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
Schedule - B

NAME OF THE WORK: Providing street name boards at chikkasanra abbigere, Mallasandra in ward no. 12 in shettyhalli sub division

Sl. No	Description of work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per the direction of Engineer-in-charge of the work	Cum	119.45	175.96	Rupees One Hundred Seventy Five and Ninety Six Paise Only
	Direction and Place Identification Signs upto 0.9 sqm Size Board:-Manufacturing, supply and installation of retro-reflectorised cautionary, mandatory and informatory signboards made out of cube corner micro prismatic grade sheeting confirming to type XI standards of IRC :67:2012 specifications & fixed over 4 mm thick aluminium composite panel sheet having minimun 0.30 thick aluminium skin on both sides & fixed over a support frame of 25x25x3 mm MS angle and mounted on 75mm dia OR 75x75x6mm Mild steel angle of total height 2.70m with clear height of not less than 2.10 m from the ground level to the bottom of the sign board & 60 cm below ground level. The sign post should be painted with one coat of red oxide paint and white colour with brands of 30 cm height alternatively firmly fixed to the ground by means of foundation with M20 grade cement concrete of 45 cm x45 cm x 60 cm including cost & conveyance of all materials, equipment, machinery & labour with all leads and lifts, loading charges necessary for satisfactory completion of the work as directed by engineer in charge. 10 years warranty for retro reflective sheeting from the original sheeting manufacturer as per clause 6.9 in IRC 2012 & a certified copy of three years outdoor exposure report from an independent test lab for the product offered shall be obtained from the supplier.	Sqm	153.00	8590.24	Rupees Eight Thousand Five Hundred Ninety and Twenty Four Paise Only
	Painting:-Providing and applying two coats of ready mix paint of approved brand after through cleaning of surface to give an even shade complete as per specifications. MORTH Specification No. 803 - Painting on Steel Surface	Sqm	205.17	60.42	Rupees Sixty and Forty Two Paise Only

Executive Engineer
Dasarahalli Division
BBMP

Signature of the Contractor

Scanned by CamScanner

4	Painting New Letter and Figures of any Shade with synthetic enamel paint black or any other approved colour to give an even shade complete as per specifications. ("i) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half)	Cm	90576.00	0.80	Eighty Paise Only
5	Removng and refixing stone slabs of drains and pointing in CM (1:3)	Sqm	324.00	80.56	Rupees Eighty and Fifty Six Paise Only
6	Removeing and resetting of kerb stones	Mtr	130.50	65.72	Rupees Sixty Five and Seventy Two Paise Only
7	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete	Nos	110.00	331.78	Rupees Three Hundred Thirty One and Seventy Eight Paise Only
8	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	36.00	5159.02	Rupees Five Thousand One Hundred Fifty Nine and Two Paise Only
9	Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications.	Sqm	82.00	993.22	Rupees Nine Hundred Ninety Three and Twenty Two Paise Only
10	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	28.80	5767.46	Rupees Five Thousand Seven Hundred Sixty Seven and Forty Six Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Dasarahalli Division
BBMP

Scanned by CamScanner

g and laying reinforced cement precast slabs of 1:11/2:3 using 20mm & down size graded granite sing HYSD 10mm dia steel @ 100 mm c/c both complete as per specifications		216.00	1680.00	Rupees One Thousand Six Hundred Eighty Only
ing and applying floor painting with ready mix paint coats (exluding priming coat) on new concrete / os cement sheet / plastered surfaces brushing to n even shade after preparing the surface after ghly cleaning oil, dirt, dust other foreign matter and papering including cost of materials, labour, lete as per specifications.	Sqm	72.00	53.00	Rupees Fifty Three Only

re of the Contractor

EXECUTIVE ENGINEER-4
BBMP DIVISION
GALURU-560 010

Executive Engineer,
Dasarahalli Division.

Scanned by CamScanner